

Due to ATEX approval requirements, remote ST98 units with a local probe enclosure will have a 1"NPT conduit port not a ¾" NPT reducer as indicated on the outline dimensional drawings.